



Table 4.3: Permissible limits on Properties I, II and III in defined-movement areas.

Floor classification	MHE lift height	Property I		Property II		Property III			
						Wheel track up to 1.5 m		Wheel track over 1.5 m	
		95%	100%	95%	100%	95%	100%	95%	100%
Superflat (SF)	Over 13 m	0.75	1.0	1.0	1.5	1.5	2.5	2.0	3.0
Category 1	8–13 m	1.5	2.5	2.5	3.5	2.5	3.5	3.0	4.5
Category 2	Up to 8 m	2.5	4.0	3.25	5.0	3.5	5.0	4.0	6.0

For all classifications, all points surveyed should be within 15 mm from datum.

PLEASE NOTE:

These are extracts from the Concrete Society's Technical Report TR34.
For further information, contact the Concrete Society on +44 (0) 1276 607140